


OHIO OIL CO.
Polcyn No. 1.SEC. 19 T. 13 R. 15 W
NE NW NE

County. Russell

Total Depth. 3377'
Comm. 3-8-43 Comp. 4-21-43
Shot or Treated.
Contractor. Sharon Drlg. Co., Inc.
Issued. 5-15-43

CASING:

8 1/4" 672' Cem.
4 1/2" 3352' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay	40	shale gy	3126
shale	80	lime	3172
shale & iron	205	lime cherty porous	3195
shale & shells	280	lime	3203
shale & sand	310	shale & lime	3210
shale & shells	370	lime	3220
shale & sand	440	shale & lime	3240
shale	455	lime cherty	3250
shale & sand	590	shale gy & maroon & lime	3270
red bed	686	lime	3275
red bed & shale	980	lime porous, slight	
anhydrite	1030	sh oil	3280
red rock	1080	lime & shale, some	
red rock & shale	1140	red rock	3298
shale	1510	lime	3308
salt & shale	1585	shale red	3311
shale	1610	lime	3340
lime & shale	1740	shale red & gy, Marmaton	3352
lime brkn	1790	chert oolitic, sand,	
lime	1875	reworked dolomite,	
shale	1915	shale	3359
lime	2015	dolomite cherty	
shale	2025	Arbuckle	3370
lime	2080	dolomite	3377
shale	2105	Total Depth.	
lime	2220		
red rock	2245		
shale & lime	2265	1100' sulphur wtr @ 3377 in	
shale	2300	3 days	
lime	2330	P.B. w/ Calseal & set L.W.	
shale	2340	plug at 3311	
lime & shale	2400	Perf. 47 holes 3104-22	
shale	2776	Bail 1 1/2 BFPH w/sh oil	
lime	2784	Dump 210 Gals. Acid	
shale	2788	Bail & swb 50 Gals. FPH,	
lime	2808	25% oil	
shale (sso 2830-35)	2828	1500 Acid	
lime Topeka	2865	Swb 8 BFPH estimated 15 to	
lime cherty	2886	50% wtr	
shale	2890	Swb 11 oil & 27 wtr 7 hrs	
lime brkn	2900	Gravity 38 deg. at 56 deg.	
lime, very lgt stain		5000 Acid	
oil	2910	Swb out load & swb 2 3/4 BO	
lime, thin shale brks	2936	& 12 1/2 BFPH for 2 hrs	
limo	2960	D & A	
lime gy & shale	2999		
lime buff-wh, fair			
stain oil	3002		
lime porous, fair sat.	3021		
lime cherty, spotted			
saturation	3046		
shale blk	3050		
shale & lime	3058		
shale gy & green	3071		
lime cherty	3078		
shale red	3082		
lime, slight oil			
stains, Kansas City	3100		
lime, fair oil stains	3120		
lime, fair por. & sat.	3123		

PLUGGING
FILE SEC. 19 T. 13 R. 15 W
BOOK PAGE 73 LINE 24

