


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS, INC.
Farm- Neil No. 1

SEC. 25 T. 13 R. 15W
SE NE SW

Total Depth. 3330'
Comm. 2-10-62 Comp. 2-18-62
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 6-2-62

County Russell
KANSAS



CASING:
8 5/8" 247' cem w/175 sx.

Elevation. 1894' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	370
sand & iron pyrite	435
shale & shells	480
redbed	922
Anhydrite	1165
shale & shells	1580
lime & shale	1895
lime	2120
shale & lime	2895
lime	3290
lime & shale	3322
lime	3330 RTD
Total Depth	

TOPS:
Topeka 2771
Heebner 2999
Toronto 3018
Lansing-Kansas City 3051
Arbuckle 3315

DST #1 3020-3035' op 30 min, rec. 6' mud.
FBHP 550#/20 min.

DST #2 3067-3085', op 1 hr, rec. 240'
muddy water. FBHP 480#/20 min.

DST #3 3089-3112', op 45 min. Rec. 70'
muddy water. FBHP 370#/20 min.

DST #4 3299-3322', op 30 min., rec. 15'
mud. FBHP 0#/20 min.

DST #5 3322-3330', op 1 hr, rec. 1250'
sulphur water. FBHP 980#/20 min.