


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company STEARNS & KISSINGER
Farm Billings "C" No. 1

SEC. 27 T. 13 R. 15W
NE NE NE

Total Depth. 3341'
Comm. 7-12-47 Comp. 11-23-47
Shot or Treated.
Contractor. Stearns Drlg. Co.
issued 4-3-48

County. Russell
KANSAS



CASING:
15 1/2" 333' P. 7" 3134' P.
13-3/8" 593' P. 5" 3339'
10" 957' P. 7" 648' Cem.
8" 2488' P UR 2602'

Elevation. 1895' Ind

Production. Pot 39 Bbls.

Figures indicate Bottom of Formations.

cellar	8	shale blue	1625	lime	2420
clay yellow	15	lime	1653	shale wh	2445
shale	20	shale	1670	lime brkn	2450
post rock	30	lime hrd	1687	lime	2460
shale gy	150	red shale	1710	shale & shells	2488
shale blue	215	lime & shells	1720	lime	2500
shale sdy	220	lime	1740	lime & shells	2505
sand wtr	245	shale	1772	shale	2555
wtr 215-45		lime	1790	shale & shells	2587
shale gy	260	lime & shells	1805	lime	2597
shale blue	270	red shale	1812	shale	2601
red shale	280	lime	1825	lime	2605
red rock	300	shale & shells	1835	shale	2610
sand	325	lime	1900	lime	2615
iron	330	shale	1915	shale & shells	2670
shale blue	333	lime	1953	lime	2675
red rock	360	shale	1965	shale & shells	2735
shale blue	370	lime	1985	lime	2770
sand wtr	375	shale	1990	shale	2775
shale gy	400	lime	2015	lime	2780
sand wtr	405	shale	2025	shale & shells	2795
shale gy	430	lime	2035	lime	2810
red rock	440	red rock	2040	shale	2815
salt wtr sand	455	shale blue	2045	lime	2875
shale blue	475	lime	2055	shale	2880
shale blue & iron	490	shale	2070	lime	2910
pyrite	500	lime	2085	shale	2915
shale blue & iron	504	lime bfrkm	2095	lime	2925
shale gy	512	shale	2100	shale	2930
shale blue	520	lime	2115	lime	2980
iron	530	shale blue	2130	shale wh	2985
shale blue & iron	535	lime	2137	lime	3015
shale blue	540	shale	2150	shale	3020
wtr sand	555	red shale	2160	shale & shells	3035
red rock	565	lime	2165	lime Dodge	3051
red rock sdy	570	red shale	2170	red shale	3055
shale	583	shale	2185	shale	3060
red sand	590	shale red	2195	shale blue	3067
iron	591	shale gy	2200	lime K. C.	3080
redrock	630	lime	2215	lime	3130
wtr sand	645	shale	2247	lime	3140
red rock sdy	730	lime	2265	shale	3205
iron	735	shale	2270	lime	3215
red rock	949	lime	2283	shale	3240
anhydrite lime	953	lime & shells	2290	lime	3270
red rock	958	lime	2305	lime brkn	3285
anhydrite lime	1000	shale gy	2310	shale	3295
red shale	1145	lime	2320	lime	3307
shale blue	1190	shale	2330	lime	3314
red shale	1265	lime	2335	shale	3316
shale blue	1312	shale	2360	lime	3328
salt	1330	lime	2365	dolomite	3338
shale blue	1350	shale	2370	dolomite oil pay	3341
salt	1550	lime	2375	Total Depth	
salt brkn	1590	shale	2385		
lime	1595	lime	2395		
		shale	2405		

Wtr 215-245
HFV 440-455

HFV 645-730
HFV 2422'

Top Arbuckle 3328
HFV 3154
Show Oil 3160
1 BW 3190-3196'