


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SHIELDS OIL PRODUCERS
 Farm- Ed Polcyn "A" No. 2

SEC. 31 T. 13 R. 15W
 NE SW SE

Total Depth. 3317'
 Comm. 1-19-55 Comp. 2-1-55
 Shot or Treated.
 Contractor. Shields Drlg Co., Inc.
 Issued. 3-26-55

County Russell
 KANSAS



Elevation. 1895 RB

Production. 25 BO

CASING:

8 5/8" 220' w/125 sx c em.
 5 1/2" 3313 1/2' w/50 sx c em.

Figures Indicate Bottom of Formations.

surface soil	15
shale-lime strks	215
shale	500
red bed	959
Anhydrite	1000
red bed-shale	1170
shale-salt strks	1240
shale-lime strks	1410
lime-shale	1885
shale	1975
lime-shale	2045
shale	2095
lime-shale	2220
shale	2320
shale-lime	2345
shale	2625
lime-shale	2834
lime	2839
shale	2853
shale-lime	2916
lime	2970
lime-shale	3065
lime	3305
Gorham sand	3313
" "	3314 RTD
Granite wash ?	3317
Total Depth	

TOPS:

Topeka	2791
Heebner	3012
Toronto (scout)	3030
Lansing-Kansas City	3060
Gorham sand	3313
Granite wash	3316