

April, 1942

Nelson, #1 Polycn
SW/c, 31-13S-15W
Elev. 1909'

Cable tools

Pennsylvanian Conglomerate 3354-3360'

3354-3358 Nodular limestone with included sand and
rare stained chert.

3358-3360 Sand, medium and coarse, part silicified.

Arbuckle Top 3360' Penetration 31' Subsea -1451'

Pre Cotter 3360'-3391' TD.

3360-3370 Dolomite, brown, medium to fine. Pre Boyce.

3370-3375 Dolomite, brown, medium. Some porosity
and oil staining. Weigel.

3375-3389 Dolomite, white and light brown, medium
rhombs, porous. Trace of dolocastic
chert. Weigel.

3389-3391 No samples.

ML & RFW