

To replace sheet of April, 1942

June, 1942

Mc Bride, # 1 Gregg
NE SE, 24-13S-15W
Elev. 1787'

Cable tools

Pennsylvanian Conglomerate

A foot or two of buff to cream finely crystalline limestone with rare imbedded sand grains rests on Arbuckle.

Arbuckle Top 3217' Penetration 10' Subsea -1430'

Pre Cotter 3217'-3227' TD Post Boyce.

3217-3221 Dolomite, fine sandy; white, brown, and pink. Spotty oil staining.

3221-3226 Dolomite, very fine, sugary to dense. Green shale partings. Oilstained.

3226-3227 Dolomite, white, variably crystalline to coarse.

Remarks: After working all available samples in 13S-14W, including about 30 tests which penetrated either low Cotter or high Post Boyce, it seemed advisable to reclassify this test.

Top of Pre Cotter estimated at 3212' or Subsea -1425'

RFW & ML