

August, 1937.

PC

Bridgeport #9 Mermis,  
NE SE SW, 33-13S-15W,  
Elevation 1895' <sup>DF</sup>  
Ls. (Printed)

Pennsylvanian conglomerate 3275-3284'  
3275-3284 Clay shales with rare sandy lime, some  
loose coarse sand, and a few fragments  
of consolidated sand. It is possible  
that there is two or three feet of  
Reagan present.

Arbuckle. There may be a few feet of Reagan present.

Pre-Cambrian Top 3284' Sub-sea, minus 1389'  
3284-3298 Granite, weathered.  
3298-3324 No samples. Reported as granite.

This test made a small well after a shot. It is possible  
that the production is coming from a few feet of Reagan or  
from fractures in the weathered granite. The material from  
3284-3298' does not look like granite wash.

3289-3306 34M

Camslys Pt 3307 <sup>cov</sup>