

2-13-16W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H. B. MABEE

SEC. 2 T. 13 R. 16W
 LOC. SW 1/4 SE

FARM Windholz

NO. 1

TOTAL DEPTH 3462'

COUNTY ELLIS


COMM. 5-4-68

COMP. 5-16-68

SHOT OR TREATED

CONTRACTOR L. J. Dreiling

ISSUED 7-20-68



CASING

20 10
 15 8 5/8" 146' cem w/ 110 sx
 12 6
 13 5

ELEVATION 1987' KB

PRODUCTION P 126 BOEPD W/GR
 Grav 40/ Lens 3342-9

4 1/2" 3450' CASING/ 125' INCREASE BOTTOM OF FORMATIONS

0'	110'	Sand & Clay
110'	143'	Blue Shale
143'	340'	Shale
340'	420'	Sand & Shale
420'	640'	Shale & Shells
640'	1107'	Shale & Shells
1107'	1150'	Anhy.
1150'	1190'	Shale & Shells
1190'	1700'	Shale & Shells
1700'	3065'	Lime & Shale
3065'	3145'	Lime & Shale
3145'	3460'	Lime
3462'	T.D.	

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Windholz #1.

Leo F. Dreiling

 LEO F. DREILING

Subscribed and sworn to before me this 17th day of May 1968.

WOB: 100

Anhydrite (s)	1107
Topeka	2935
Heebner	3155
Coronto	3174
Jensin	3205
Base Kansas City	3452
Arbuckle	3458
LTD	3462
RTD	3462