

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

4-13-16W


Company- RUPP-FERGUSON OIL CO.
Farm- Madden No. 1

SEC. 4 T. 13 R. 16W
SE SE SW

Total Depth. 3503'
Comm. 6-8-54 Comp. 6-17-54
Shot or Treated.
Contractor. Rupp-Ferguson Oil Co.
Issued. 7-24-54

County Ellis

KANSAS



CASING:
8" 253'

Elevation. 1982' KB

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	400
sand streaks, gravel	
& shale	690
sand	760
red bed & shale	1110
shale & shells	1425
shale, shells & salt	1765
shale & lime	2785
lime, shale & sand strks	2941
lime & shale	3250
lime	3442
lime & shale	3474
Arbuckle	3496
lime	3503
Total Depth	

Tops:	
Heebner	3167
Toronto	3188
Kansas City-Lansing	3216
Base Kansas City	3408
Arbuckle	3467

DRILL STEM TESTS:

#1 3235-3250, open 1 hr., rec. 15' muddy
salt water. BHP 340#.