

6-13-16W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

SAN JUAN OIL CO. &
Company- STERLING DRILLING CO.
Farm-Hammerschmidt No. 1

SEC. 6 T. 13 R. 16W
SE NW NW

Total Depth. 3564
Comm. 5-30-57 Comp. 6-10-57
Shot or Treated.
Contractor. Sterling Drilling Co.
Issued. 7-27-57

County Ellis
KANSAS



CASING:
8 5/8 @ 200' w/ 125 sx cmt.

Elevation. 2009 RB

Production. Dry

Figures indicate Bottom of Formations.

rock & shale	100
shale & shells	410
shale & sand	1040
shale	1160
anhydrite	1200
shale & red bed	1335
shale & shells	1735
shale & lime	2100
lime	2250
lime & shale	3000
lime	3105
lime & shale	3195
lime	3482
shale & lime	3512
conglomerate	3523
lime	3564
Total Depth	

TOPS:

Heebner	3202
Toronto	3223
Douglas	3235
Lansing	3248
Conglomerate	3507
Arbuckle	3549

DST #1: 3252-90, open 50 min. SI 30 min. wk. bl 20 min. rec. 25' mud FP 50-50#, BHP 80#

DST #2: 3301-50, open 1 hr. SI 30 min. wk. bl thruout, rec. 40' thin mud, FP 0-30#, BHP 1010#

DST #3: 3428-82, open 45 min. Si 30 min. wk. bl. 15 min. rec. 18' mud, FP 0-0#, BHP 135#

DST #4: 3503-23, open 45 min. SI 30 min. wk. bl. 9 min. rec. 10' mud. FP