

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-13-16W

Company- TENNESSEE GAS TRANSMISSION CO.
Farm- Froelich No. 1

SEC. 4 T. 13 R. 16W
NE SW NW

Total Depth. 3520'
Comm. 10-24-56 Comp. 11-7-56
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 12-1-56

County Ellis
KANSAS



Elevation. 1991' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale-sand	201
shale	700
sand	770
shale-red bed	830
shale-shells	1125
Anhydrite	1160
shale-red bed	1700
shale-shells	1795
limestone-shale	1960
limestone	2415
shale-limestone	2600
shale	2815
shale-limestone	2950
limestone	3165
limestone-shale	3215
limestone	3473
shale-limestone	3485
limestone	3520
Total Depth	

TOPS:

Heebner	3172
Toronto	3193
Lansing	3221
Conglomerate	3465
Arbuckle	3471

DST #1 - 3245-57, open 1 hr.,
SI 20", rec. 90' gas, 70'
fluid(10' HO&GCM, 30' SO&GCM
30' SO & WCM), BHP 400.

DST #2 - 3276-91, open 1 hr.,
SI 20", rec. 12' mud, 0 BHP.

DST #3 - 3468-73, open 1 hr.,
SI 20", re. 75' oil specked mud,
BHP 585

DST #4 - 3465-85, open 1 hr., rec.
120' gas, 40' SOCM, 60' thin mud,
20" BHP 725#

DST #5 - 3464-89, open 1 hr.,