

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


12-13-16W

Company- W. F. WEIGEL
Farm- Polcyn No. 1

SEC. 12 T. 13 R. 16W
NE SE SW

Total Depth. 3400'
Comm. 4-14-53 Comp. 4-24-53
Shot or Treated.
Contractor.
Issued. 5-16-53

County Ellis
KANSAS



CASING:
8 5/8" 170' cem w/100 sx.

Elevation. 1905 RB
(1902 RB)

Production. Dry

Figures Indicate Bottom of Formations.

ALL MEASUREMENTS R.B.

soil sand, post rock	60
shale blue, shells	170
shale, lime, shells	397
iron pyrite, sand hard	442 ✓
sand hard, shale	540
shale, shells	575
sand	580
shale red bed	984
anhyd.	1000
anhyd.	1023
shale, shells	1320
shale, lime	1967
lime	2190
lime, shale	2890
lime	3365
congl.	3400
Total Depth	

Scout-Tops	
Anhyd.	984
Topeka	3777
Heebner	3035
Kansas City	3085
Marmaton	3329
Congl.	3360

DST 2990-3030 tool open 1 hr. rec. 75' slightly oil cut muddy salt wtr. Med. to weak flow throughout test 20 min. BHP 885 #1

DST 3103-3160 tool open 1 hr. 40 min. rec. 90' slightly oil cut muddy salt wtr. Med blow throughout test. 20 Min. BHP 675#

No elec. log run.