


Company - MIDSTATES OIL CORP. & BARNETT OIL CO.
Farm - Dordland No. 1

SEC. 14 T. 13 R. 16W
SE SE NE

Total Depth. 3450
Comm. 2-28-50 Comp. 3-17-50
Shot or Treated.
Contractor.
Issued. 4-15-50

County. Ellis
KANSAS



CASING:
8 5/8" 165' cem w/125 sx.

Elevation. 1947 *and*

Production. dry

Figures Indicate Bottom of Formations.

surface clay, shae	40
surface clay	75
sand	95
shale, shells	460
sand	510
sand, shale	750
shale & shells	1010
shale & sand	1040
lime	1055
shale, shells	1525
salt, shale	1650
shale, shells	1900
lime, shale	2420
shale	2670
lime, shale	2905
lime	3051
lime, shale	3090
lime	3450
Total depth	

Tops:	Sample	Electric
Topeka	2862	2828
Heebne	3082	3080
Lansing	3127	3131
Cherty Congl.	3384	3384
Arbuckle	3396	3398
Total depth	3448	3440

OIL SHOWS:

Kansas City- 3174-80, 3201-03, 3242-44,
3263-72, 3287-88, 3299', all spotted
stains. Also 3307-08, 3310-11, 3318-20 & 3331.
Arbuckle - 3398-3400, Sat & free oil.
3416-33, dead stain.