



Lease Name: VON LINTEL 'B' Well No. 1
 Well Located: NW SW NE
SEC 18 TWP 13S RGE 16W
 Operator: Petroleum, Inc.
 Address: Wichita, Kansas
 Elevation: Ground 1990' D.F. 1993' K.B. 1995'
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: February 2019 72 Drilling Completed: February 2819 72
 Well Completed: February 2819 72 Total Depth RTD 3565
 Initial Production: _____

Casing Record

Size: 8-5/8" Set at 252' Size: _____ Set at _____
 Size: _____ Set at _____ Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8-5/8"</u>	<u>175</u>	<u>Regular 2% Gel, 2% Calcium</u>
_____	_____	_____
_____	_____	_____

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
_____	_____
_____	_____
_____	_____
_____	_____

Electric Log Run. (Show type log and depths covered)

Dresser Atlas Gamma Ray-Neutron-Laterolog w/Caliper (3565 - 0)

(Fill in formation and related information on reverse side)

18-13-16w

FORMATION, TESTING AND COMPLETION RECORD

Formation	Top	Bottom	Show Drill Stem Tests, Well Stimulation and Production Tests
<u>E. L. TOPS:</u>			
Heebner Toronto Lansing B/KC ELTD	3207 3227 3259 3485 3566	-1212 -1232 -1264 -1490 -1571	DST #1: 3314-33: 30-30-30-60; Weak Blow; recovered 40' Oil Cut Mud; 1FP 27#-32#, 1BHP 603#, 2FP 32#-36#, 2BHP 622# DST #2: 3431-70: 30-30-30-60; Very Weak Blow; recovered 30' Mud; 1FP 27#-32#, 1BHP 54#, 2FP 32#-36#, 2BHP 59# DST #3: 3482-3565: 30-30-30-30; Strong Blow; 2150' Mud w/trace of Free Oil; 1FP 622#-822#, 1BHP 931#, 2FP 849#-913#, 2BHP 940#