


19-13-16W

Company - GULF OIL CORP.
Farm - Margaret No. 1

SEC. 19 T. 13 R. 16 W
CS $\frac{1}{2}$ NE SE

Total Depth. 3527 PB 3520
Comm. 3-9-45 Comp. 4-23-45
Shot or Treated.
Contractor.
Issued. 9-15-45

County. Ellis
KANSAS



CASING:
8 5/8" 1126' Cem. LI
5 1/2" 3510' Cem. LI
4 1/2" 3520'

Elevation. 1972 sh.

Production. Pot. Pump. 6BO & 1 BW

Figures Indicate Bottom of Formations.

surface	0-55
surface sand & shells	340
shale, sand & shale	580
shale	630
sand	690
shale	825
shale & red bed	1118
anhydrite	1130
shale & shells	1490
salt & shale	1660
shale & sand	1925
lime, brkn & shale	2010
lime	2183
lime sdy	2255
lime	2460
lime brkn	2535
lime	2575
lime brkn	2680
shale & shells	2800
lime	2945
shale & shells	2955
Topeka Lime	2977
lime	3025
lime Topeka	3095
lime	3218
lime & shale	3273
K. C. Lime	3316
lime	3394
lime & cherty lime	3417
cherty lime	3435
lime	3502
conglomerate	3509
Arbuckle lime	3512
lime	3514
lime sft	3520
lime	3527

Total Depth PB 3520

Perf. formation 4-18-45 w/
48 shots 3512-19 1/2

Acidized 3-29-45 w/1000 gals
Acidized 3-31-45 w/5000 gals
Acidized 4-19-45 w/5000 gals

Tops:

Lansing 3262
Base Kans. City 3488
Arbuckle 3509

Liner Perf 3512-19 1/2