

17-12-16W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Bldg., Wichita, Kansas

Company GULF OIL CORPORATION
Farm A.D. Dreiling No. 2

SEC. 19 T. 13 R. 16W
C S/2 SW SE

Total Depth. 3527'
Comm. 12-26-47 Comp. 1-15-48
Shor or Treated.
Contractor.
Issued. 3-6-48

County. Ellis
KANSAS



CASING:
8 5/8" 1133' cem. 466 sx.

Elevation. 1977 Ind

Production. Dry

Figures Indicate Bottom of Formations.

clay, shale & shells	40
shale & shells	635
sand	750
shale & shells	775
shale	935
red bed & shells	995
red rock	1098
red rock & chalk	1122
anhydrite	1200
shale & lime	1390
shale & shells	1520
salt	1675
shale	1800
shale & lime	1830
lime & shale	2105
lime	2620
shale & lime	2940
lime	2980
lime & shale	3030
shale & lime	3065
lime	3115
shale & lime	3130
lime	3497
conglomerate, cherty	3520
conglomerate	3524
arbuckle lime	3527
Total Depth.	

TOPS:

Heebner	3200
Toronto	3220
Base Oread	3238
Lansing <i>Lansing</i>	3247
BKC	3478
P B C	3495
Arbuckle	3523