


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DON E. PRATT
Farm- J. Dreiling No. 1

SEC. 21 T. 13 R. 16W
NW SW SW

Total Depth. 3528'
Comm. 12-23-60 Comp. 1-5-61
Shot or Treated.
Operator. H-30, Inc.
Issued. 3-26-61

County Ellis KANSAS



Elevation. 1974' DE

Production. Dry

CASING:
8 5/8" 171' cem w/135 sx.

Figures Indicate Bottom of Formations.

surface soil & clay	30
shale	171
shale & shells	400
sand	460
shale & shells	610
sand	745
shale & shells	1093
Anhydrite	1131
shale, red bed & shells	1415
shale	1775
lime & shale	2533
shale & shells	2730
lime & shale	3120
lime	3194
lime & shale	3277
KC lime	3285
lime & shale	3341
KC lime	3403
lime & shale	3453
lime, shale & chert strks	3491
lime & shale	3504
cherty lime & shale	3509
Arbuckle	3528 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1093
Base Anhydrite	1131
Topeka (scout)	2953
Heebner	3172
Toronto (scout)	3192
Kansas City	3221
Base Kansas City (scout)	3455
Conglomerate (scout)	3473
Simpson (scout)	3481
Arbuckle	3498