


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Louis M. Mai Operations
Farm- Dinkel No. 6

SEC. 22 T. 13 R. 16W
C S/2 SW/4

Total Depth. 3480'
Comm. 10-25-62 Comp. 11-6-62
Shot or Treated.
Contractor. Mast Drilling
Issued. 4-6-63

County Ellis
KANSAS



CASING:

8 5/8" 247' cem w/175 sx. of Pos. HA.5
5 1/2" 3470' cem w/100 sx. of Pos. & 45 gal. Latex

Elevation. 1960' KB

Production. 10 BO, 5 BWPD

Figures Indicate Bottom of Formations.

sand	30
sandy shale-post rock	160
shale	565
sand	715
red bed	1072
Anhydrite	1112
shale-sand	1770
lime w/ shale stks.	1908
lime	2250
shale	2375
lime-shale	2550
shale	2795
lime-shale	2988
lime	3475
sand	3480 RTD
Total Depth	

TOPS: SAMPLE

Topeka	2942
Heebner	3160
Toronto	3181
Lansing Kansas City	3207
Base Kansas City	3445
Conglomerate Sand	3467-77