

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Brungardt No. 1

SEC. 25 T. 13 R. 16W
SE SW SE

Total Depth. 3414'

Comm. 9-20-63


Comp. 9-28-63

Shot or Treated.

Contractor.

Issued. 1-25-64

County Ellis
KANSAS



Elevation. 1919' DF

Production. 83 BOPD NW

CASING:

8 5/8" 245' cem w/175 sx.

5 1/2" 3405' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface clay	40
shale & shells	545
sand	635
shale & redbed	986
Anhydrite	1026
shale & shells	1660
shale & lime	2945
lime	3040
lime & shale	3110
lime	3414 RTD
Total Depth	

TOPS: LOG

Anhydrite	986
Base Anhydrite	1026
Heebner	3058
Toronto	3078
Lansing	3104
Arbuckle	3396

DST #1 3091-3116 Op 20", weak blow 3",
flushed tool, had weak blow 4", Rec. 20'
mud. IBHP 495#, FBHP 93#, IFP 23#, FFP
31#.

DST #2 3144-91' Op h hr., SI 15" on both
ends, ahd gas to surface in 10", Rec. 1700'
gassy oil, IBHP 740#, FBHP 670#, IFP 217#,
FFP 529#.

DST #3 3201-12' Op 1 hr., SI 20" on both
ends, had weak blow 7", Rec. 12' mud.
IBHP 754#, FBHP 673#, IFP 32#, FFP 48#

DST #4 3353-3403' Op 20", SI 20" on both
ends, wk. blow 7", Rec. 15" mud. IBHP
276#, FBHP 153#, IFP 51#, FFP 64#.