

MAR 7 1970

Shields


WELL LOG

26-13-16W

Russell, Kansas

Operator: Joseph Furthmyer
 Well: Furthmyer #1
 Commenced: February 1, 1970
 Completed: February 8, 1970
 Contractor: Shields Drilling Co., Inc.

Well Description: SW SW NE
 Sec. 26-13S-16W
 Ellis County, Kansas



CASING RECORD
 Size Run Pulled
 8 5/8" 219' Cmtd. w/ 140 sax

Elevation: 1,913' RB
 Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Shale, rock & sand streaks	225'	
Shale & sand	620'	
Shale & redbed	997'	
Anhydrite	1,036'	
Shale, shells & salt	1,415'	
Shale	1,675'	
Shale, shells & lime	1,815'	
Lime & shale	2,872'	
Lime	3,412'	
Conglomerate	3,450'	RTD

Geology Report

Contractor: Shields Drilling Co.
 Elevation: 1913 R.B.
 Casing: 219' of 8 5/8" surface
 Commenced: 2-1-70
 Completed: 2-8-70.
 Drilling tests: 2 Reinhardt Services Inc Both negative
 Well status: Dry & Abandoned.

Anhydrite	997	+ 916
Topika Lime	2870	- 957
Hunter Shale	3087	- 1174
Toronto Lime	3107	- 1194
Lansing-KC	3135	- 1222
Base of Lansing/KC	3377	- 1464
Conglomerate	3395	- 1482
Total Depth	3450-	- 1537

Notes

yours truly
 Joseph Furthmyer