


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- DON E. PRATT
 Farm- Pratt Air Base No. 9

SEC. 28 T. 13 R. 16W
 SE NW NE

Total Depth. 3523'
 Comm. 12-3-60 Comp. 12-13-60
 Shot or Treated.
 Operator. H-30, Inc.
 Issued. 8-26-61

County Ellis KANSAS



CASING:
 8 5/8" 165' cem w/135 sx.
 4 1/2" 3519' cem w/225 sx.

Elevation. 1970' DF

Production. 100 BOPD

Figures Indicate Bottom of Formations.

surface soil & sand strks	30
shale & shells	580
sand	730
shale & shells	920
shale & red bed	1040
shale & shells	1078
Anhydrite	1120
shale, red bed & shells	1480
shale & shells	1665
shale w/line strks	1800
lime w/shale strks	1920
lime & shale	2490
shale & lime	3154
lime & shale	3220
KC lime	3256
lime	3300
KC lime	3315
lime & shale	3364
lime	3402
KC lime	3473
Cherty Conglomerate	3516
Arbuckle	3523 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1078
Base Anhydrite	1120
Heebner	3168
Toronto (scout)	3189
Kansas City	3218
Base Kansas City (scout)	3452
Conglomerate	3466
Conglomerate Sand	3483
Arbuckle	3516