


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DON E. PRATT
Farm- Pratt Air Base No. 10

SEC. 28 T. 13 R. 16W
SE SW NE

Total Depth. 3507'
Comm. 12-13-60 Comp. 12-23-60
Shot or Treated.
Contractor. H-30, Inc.
Issued. 8-26-61

County Ellis
KANSAS



Elevation. 1967' DF

Production. 85 BOPD

CASING:

8 5/8" 168' cem w/135 sx.
5 1/2" 3503' cem w/200 sx.

Figures Indicate Bottom of Formations.

top soil	10
sand, gravel & rock	85
shale	169
shale & shells	560
sand	710
red bed, shale & shells	1079
Anhydrite	1118
red bed, shells & shale	1490
shale	1780
lime & shale	1820
shale & shells	1890
lime	1970
lime & shale	2055
lime	2135
lime & shale	2880
shale	2945
lime w/shale	3000
lime & shale	3205
KC lime	3228
lime & shale	3268
KC lime	3290
lime, chert & shale	3332
KC lime	3399
lime & shale	3455
cherty conglomerate	3505
Arbuckle	3507 RTD
Total Depth	

TOPS: ELECTRIC

Anhydrite	1077
Base Anhydrite	1114
Topeka	2941
Heebner	3160
Toronto	3181
Lansing	3210
Kansas City Base	3442
Conglomerate	3454
Arbuckle	3502