

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY AMERICAN PETROFINA OF TEXAS

SEC. 28 T. 13 N. 16W  
 LOC. C SE SE

FARM Pratt Airbase NO. 21

TOTAL DEPTH 3495'  
 COMM. 12-12-66 COMP. 12-21-66  
 SHOT OR TREATED  
 CONTRACTOR Leben Drlg.  
 ISSUED 3-4-67

COUNTY Ellis  
 KANSAS



CASING

20	10	
15	8 5/8" 205'	cem w/ 150 sx
12	6	
13	5" 34'93"	

ELEVATION 1961' KB

PRODUCTION 40 BOPD PLUS 20% W  
 Cogs 3458-60

FIGURES INDICATE BOTTOM OF FORMATIONS

0	60	Surface Soil, Sand, Postrock
60	205	Shale
205	385	Shale, Redbed
385	680	Sand, Pyrite
680	695	Sand
695	1060	Redbed
1060	1100	Anhydrite
1100	1273	Shale
1273	1760	Shale, Shells
1760	3155	Lime, Shale
3155	3470	Lime
3470	3493	Lime, Shale
	<u>3493</u>	<u>RTP - Set 5 1/2" Casing</u>
	3495	Total Depth

8 5/8" 24# 8 rd. used surface casing @ 205' cemented with 150 sacks Quickset cement

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Pratt Airbase #1 well, located C SE SE of Section 28, Township 13 South, Range 16 West, Ellis County, Kansas.

*Leslie Kite*  
 \_\_\_\_\_  
 Leslie Kite

TOPS: SCOUT

Topeka	2895
Heebner	3151
Toronto	3170
Lansing	3200
Base Kansas City	3442
Conglomerate	3448
Arbuckle	None