


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

GULF OIL CORP.
Elizabeth Brungardt No. 2.

SEC. 31 T. 13 R. 16 W
CN $\frac{1}{2}$ SW NE

Total Depth. 3478'
Comm. 7-12-43 Comp. 8-3-43
Shot or Treated.
Contractor.
Issued. 11-6-43

County. Ellis



CASING:
8 5/8" 201' Cem.
5 1/2" 3462' Cem.

Elevation.

Production. Pot. 155 B.
No wtr

Figures Indicate Bottom of Formations.

surface clay	0-39
shells & shale	300
sand	330
shale & shells	510
shale	727
shale & shells	935 1035
anhydrite	1000
lime & shale	1100
lime	1134
shale	1200
shale & shells	1275
red bed & shale	1340
shale & shells	1420
salt	1635
shale & shells	1770
lime & shale strks	1870
lime & shale	1985
lime	2050
lime brkn & shale	2090
lime & shale strks	2170
lime & shale	2177
lime cherty	2230
lime	2270
lime brkn & shale	2505
lime & shale	2605
shale & lime strks	2725
shale & lime	2825
shale	2910
lime & shale	3461
lime Arbuckle	3478
Total Depth.	

Acidized 7-31-43 w/1200 Gals.
Acidized 8-3-43 w/2000 Gals.

Tops: Toronto 3186
Base Oread 3199
Lansing 3208
Arbuckle (Corr.) 3461

3462=3464