


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ARTNETL COMPANY  
Farm- Brungardt No. 1

SEC. 31 T. 13 R. 16W  
NE SE NE

Total Depth. 3485' PB 3263'  
Comm. 12-28-55 Comp. 1-9-56  
Shot or Treated.  
Contractor. Prime Drlg. Co.  
Issued. 5-17-58

County Ellis  
KANSAS



Elevation. 1961' RB

Production. 296 BOPD

CASING:

8 5/8" 204' cem w/145 sx.  
5 1/2" 3466' cem w/150 sx.

Figures indicate Bottom of Formations.

surface rock & clay	30	
shale stks, iron	204	✓
shale, shells stks, iron	290	✓
shale, shell & red bed & iron	610	✓
sand	725	
shale, red bed & shell	1040	
shale & shells	1080	
Anhydrite	1115	
shale & shells	1720	
shale & lime	3030	
lime	3070	
lime & shale	3145	
lime	3460	
lime, shale & chat	3473	RTD
lime	3485	
Total Depth		
Plugged back to 3263'		

TOPS: SCOUT  
Anhydrite 1080  
Lansing 3210  
Arbuckle 3464

Perforated w/12 shots from 3245-3248.  
Treated w/500 gal. regular, and 1000 gal.  
retarded acid.