

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- CARL TODD DRILLING CO.
Farm- Braun No. 1

SEC. 32 T. 13 R. 16W
NW SW NW

Total Depth. 3480
Comm. 10-20-55 Comp. 10-29-55
Shot or Treated.
Contractor. Carl Todd Drilling Co.
Issued. 1-14-56

County Ellis

KANSAS



Elevation. 1952 KB

Production. 473 BOPD

CASING:

8 5/8 @ 200' w/ 135 sx cmt.
5 1/2 @ 3474' w/ 100 sx cmt.
DV tool @ 1075' w/ 350 sx cmt.

Figures indicate Bottom of Formations.

clay & shale	60
shale & shells	505
shale & iron	620 ✓
shale & red bed	750
shale & sand	880
shale & shells	1065
anhydrite	1100
shale & shells	1125
shale & salt	1555
shale & shells	1770
lime & shale	1950
shale & shells	2090
shale & lime	2205
iron & shale	2215 ✓
shale & lime	2290
shale & shells	2400 ✓
shale, lime & iron streaks	2530 ✓
shale & shells	2810
shale & lime	2950
lime	3030
lime & shale	3100
shale	3140
lime	3165
shale & lime	3198
lime	3480
Total Depth	

TOPS:

Heebner	3156
Dodge	3178
Lansing	3198
Conglomerate	3447
Arbuckle	3474

DST #1: 3222-35, open 1 hr. gas to surf. 20 min. rec. 2000' gassy oil, no water, IFP 0#, FFP 480#, BHP 780#

DST #2: 3374-3408, open 1 hr. faint bl. 3 min. rec. 10' mud, BHP 0#