


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CARL TODD DRILLING CO.
Farm- Braun No. 2

SEC. 32 T. 13 R. 16W
CE/2 SW NW

Total Depth. 3496'
Comm. 3-19-56 Comp. 3-28-56
Shot or Treated.
Contractor.
Issued. 6-9-56

County Ellis
KANSAS



CASING:
8 5/8" 212' cem w/150 sx
5 1/2" 3496' cem w/125 sx

Elevation. 1935' RB

Production. 422 BOPD

Figures indicate Bottom of Formations.

sand and gravel	30
shale & shells	385
sand and gravel	440
shale	460
sand and pyrite	525 ✓
blue shale & shells	700
red bed	840
red bed and shale	1055
anhydrite	1090
shale, shells, red bed	1250
shale, shells, salt	1660
shale and lime	3203
lime	3386
lime and shale	3436
lime	3496 RTD
Total Depth	

Tops:
Heebner 3138
Toronto 3158
Lansing-Kansas City 3181
Base Kansas City 3415
Conglomerate 3427
Arbuckle 3490

DST #1 3178-3203', open 1 hr., rec. 2070'
gas, 90' frothy oil and gas cut mud,
120' muddy oil, 180' clean oil. IF 0, FF 0,
BHP 530# in 20 min.

DST #2 3223-40', open 1 hr., rec. 25' muddy
salt water, specks of oil. BHP 905# in 20 min.