

Location NW cor NE SE.

Sec. 1 T. 13 R. 16W.

Casing Record

County- Ellis

10" 970 Farm- J. Perschisnke No. 1
 20" 8 1/4" 2788 Company- Davis-Hazlett et al.
 15 3/8" 385 65/8" 3062 Contr.- James Davis.
 12 3/8" 569 53/16" Comm.- 9/30/30. Comp.- 11/11/30.
 Total Depth 3320'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production Dry.

Date Issued. 12/20/1930

Formation	Depth	Formation	Depth	Formation	Depth
cellar	15	slate	2030	Caving 2780'-Lowered 8"	
clay yellow	30	lime	2050	to 2788'.	
slate drk	235	slate	2065	lime	2800
sand water	260	red rock	2070	Carrying 3 BW	
HFW 235-260'		lime	2085	brkn lime	2830
slate blue	285	slate	2095	lime	2875
slate white	300	lime	2110	slate	2880
red rock	325	slate & shells	2130	lime	2915
slate	335	lime	2140	slate	2920
red rock	400	slate	2150	lime	3020
sand	405	lime	2170	Good show oil 2965-2970'	
red rock	415	slate	2180	slate	3025
slate drk	455	red rock	2205	lime Dodge	3035
sand	465	lime sft	2215	lime	3046
slate blue	485	1 1/2 BW 2205-2215'		shale red	3055
sand	490	lime hrd	2235	slate blue	3062
slate blue	500	slate	2245	lime Oswald	3082
sand	505	lime	2260	SLM lgt show oil 3072'	
slate & iron	520	slate & shells	2280	slate	3088
slate	545	lime	2290	lime sft	3093
lime	550	slate & shells	2310	Good show oil 3088-3092'	
slate 12 1/2" set 557'	555	lime brkn	2335	lime	3103
12 1/2" lowered to 569'		slate	2345	slate	3104
slate blue (HFW 585-	585	lime	2350	SLM 3102-3104	
sand water 600')	600	slate & shells	2390	lime	3125
sdv lime	618	slate	2435	slate	3129
slate	625	lime hrd	2445	lime sft	3135
red rock	968	slate drk	2455	Free oil 3129-3135'	
lime	975	Hole caving		HFW 3140-47'	
lime	1005	slate & shells	2480	lime	3185
red rock	1100	slate	2495	brkn lime	3200
slate blue	1110	sand	2500	lime hrd	3260
red rock	1135	Show gas 2495-2500		slate	3265
slate blue	1150	Hole caving		lime	3309
slate	1175	slate & shells	2515	slate blue	3320
red rock	1255	gas sand	2522	Total Depth	3320
slate blue	1290	3 M. cu. ft Gas			
salt	1595	2515-2522			
slate	1620	slate & shells	2545		
lime	1650	slate & shells	2572		
slate	1680	lime	2575		
lime	1700	slate & shells	2600		
slate	1710	lime	2605		
lime	1720	slate	2610		
slate	1740	slate & shells	2645		
red rock	1755	lime	2655		
lime	1780	slate	2665		
slate	1790	lime	2670		
red rock	1800	slate & shells	2695		
lime	1845	slate	2705		
red rock	1880	sdv shale	2710		
lime	1900	3 BW 2705-2710'			
slate	1915	slate & shells	2735		
lime	1950	lime	2745		
Carrying 1/4 BW per hr		slate	2750		
slate	1955	Hole caving 2750'			
lime sdv	1980	lime	2767		
slate	1985	slate	2770		
red rock	2000	lime hrd	2773		
lime	2015	slate	2788		