

JAMES C. MUSGROVE

Petroleum Geologist
P.O. Box 1162
Great Bend, KS 67530

Office (620) 792-7716

Res. Claflin (620) 587-3444

White Eagle Resources Corp.
Wolf #8
60' North W/2-NW-NW; Section 4-13s-17w
Ellis County, Kansas
Page No. 1

5 1/2" Production Casing Set

Contractor: Southwind Drilling Company (Rig #1)

Commenced: June 23, 2005

Completed: June 30, 2005

Elevation: 2086' K.B.; 2084' D.F.; 2076' G.L.

Casing Program: Surface; 8 5/8" @ 237'
Production; 5 1/2" @ 3689'

Samples: Samples saved and examined 2950' to the Rotary Total Depth.

Drilling Time: One (1) foot drilling time recorded and kept 2950' to the Rotary Total Depth.

Measurements: All depths measured from the Kelly Bushing.

Formation Testing: There were four (4) Drill Stem Tests ran by Trilobite Testing Company.

Electric Log: By Log Tech; Dual Induction, Dual Compensated Porosity Log and Micro.

Gas Detector: None.

<u>Formation</u>	<u>Log Depth</u>	<u>Sub-Sea Datum</u>
Anhydrite	1276	+810
Howard	2978	-882
Topeka	3033	-947
Heebner	3286	-1200
Toronto	3304	-1218
Lansing	3328	-1242
Arbuckle	3589	-1503
Rotary Total Depth	4440	-1604
Log Total Depth	4483	-1607

(All tops and zones are corrected to Electric Log measurements).

SAMPLE ANALYSIS, SHOWS OF OIL, TESTING DATA, ETC.

TOPEKA SECTION

3216-3221' Limestone; cream, gray, finely crystalline, slightly chalky, poor visible porosity, no shows.

3228-3236' Limestone; tan, cream, chalky, scattered pinpoint porosity, trace stain, no show of free oil and questionable odor in fresh samples.

ORIGINAL

- 3260-3266' Limestone; cream, white, fossiliferous, chalky, trace dark brown to brown stain, trace of free oil and faint odor in fresh samples, trace gray, fossiliferous chert.
- 3274-3278' Limestone; gray, cream, chalky, trace brown stain, trace of free oil and no odor in fresh samples.

TORONTO SECTION

- 3304-3314' Limestone; cream, white, fossiliferous, poorly developed porosity, trace gray to brown spotty stain, trace of free oil and questionable odor in fresh samples.

LANSING SECTION

- 3328-3336' Limestone; cream, buff, few fossiliferous, poorly developed porosity, trace poor brown edge staining, no show of free oil or odor in fresh samples.
- 3358-3364' Limestone; tan, brown, fine to medium crystalline, fossiliferous, trace brown stain, trace of free oil and no odor in fresh samples.
- 3376-3380' Limestone; white, gray, fossiliferous, chalky in part, fair to good light brown to golden brown stain, trace of free oil and questionable odor in fresh samples.

Drill Stem Test #1 3281-3384'

Times: 30-45-45-60

Blow: Strong, decreasing

Recovery: 800' mud

Pressures: ISIP 768 psi
FSIP 463 psi
IFP 300-352 psi
FFP 369-383 psi
HSH 1543-1497 psi

Remarks: Lost circulation at 3363', tested, lost circulation zone.

- 3402-3406' Limestone; gray, white, highly fossiliferous, oolitic, fair porosity, brown to light brown stain, show of free oil and faint odor in fresh samples.
- 3410-3414' Limestone; gray, cream, oolitic, fair to good vuggy type porosity, golden brown to brown stain, show of free oil and faint odor in fresh samples.
- 3421-3428' Limestone; gray, oomoldic, fair to good oomoldic porosity, fair to good brown stain and saturation, show of free gassy oil and faint odor in fresh samples.

Drill Stem Test #2 3379-3431' **Misrun**

Drill Stem Test #3 3390-3431' **Misrun**

ORIGINAL

- 3490-3500' Limestone; cream, oolitic, poorly developed porosity, trace brown to golden brown spotty stain, no show of free oil and questionable odor in fresh samples.
- 3512-3517' Limestone; gray, white, oomoldic, slightly chalky, fair brown to dark brown stain, show of free oil and good odor in fresh samples.
- 3534-3544' Limestone; gray, cream, fossiliferous, sub oomoldic, poorly developed porosity, trace poor spotty edge staining.
- 3555-3564' Limestone; gray, white, chalky, few fossiliferous, chalky, trace gray to black stain, no show of free oil or odor in fresh samples.

ARBUCKLE SECTION

- 3689-3694' Dolomite; cream, gray, medium crystalline, fair intercrystalline porosity, few cherty, trace brown stain and saturation, show of free oil and faint odor in fresh samples.
- 3694-3600' Dolomite; gray, tan, medium crystalline, scattered porosity, trace brown to golden brown and dark brown stain, trace of free oil and faint odor in fresh samples.
- 3604-3607' Dolomite; tan, brown, finely crystalline, sucrosic, fair to good pinpoint to vuggy porosity, good brown to dark brown stain and saturation, fair to good show of free oil and good odor in fresh samples, trace of chert, white, clear, recrystallized, fair to good brown stain and saturation, show of free oil.

Drill Stem Test #4 3563-3607'

Times: 30-30-60-60

Blow: Weak

Recovery: 15' clean oil
60' muddy oil
(80% oil, 20% mud)

Pressures: ISIP 769 psi
FSIP 747 psi
IFP 17-26 psi
FFP 28-42 psi
HSH 1741-1656 psi

- 3607-3612' Dolomite; tan, finely oomoldic, fair to good porosity, good stain and saturation, good show of free oil and fair odor in fresh samples.
- 3616-3625' Dolomite; tan and gray, fine to medium crystalline, few sucrosic, few 100% stain and saturation, fair to good show of free oil and good odor in fresh samples, trace white and gray, cherty, dense, dolomite and white chert.
- 3625-3650' Dolomite and chert; as above, trace iron pyrite.

3650-3660'	Dolomite; tan, beige, finely crystalline, sucrosic, scattered pinpoint to intercrystalline type porosity, brown to black stain, show of free oil (flakey/gummy) and fair odor in fresh samples.
3660-3670'	Dolomite; as above, trace pink finely crystalline dolomite, few sandy, black stain, show of free oil (black, flakey) and fair odor in fresh samples.
3670-3693'	Dolomite; gray, white, finely crystalline, few sucrosic, fair to porosity, black to gray stain, show of free oil (dead) and faint odor in fresh samples, trace white chert and iron pyrite.


Rotary Total Depth	3690 (-1604)
Log Total Depth	3693 (-1607)

Recommendations:

On the basis of the favorable structural position and the positive results of Drill Stem Test #4, it was recommended by all parties involved to set and cement 5 ½" production casing at 3692' (one foot off bottom, log measurements) and the following zones be tested in the Wolf #8:

- | | |
|-------------|------------|
| 1. Arbuckle | 3605-3608' |
| 2. Arbuckle | 3596-3599' |
| 3. Lansing | 3513-3517' |
| 4. Lansing | 3422-3428' |
| 5. Lansing | 3410-3414' |
| 6. Lansing | 3358-3366' |

Respectfully submitted;


James C. Musgrove
Petroleum Geologist

