

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

OHIO OIL COMPANY.
Joseph Karlin No. 1.

SEC. 10 T. 13 R. 17W.
NEc NW

Plotted Texas CO.


County Ellis.

Total Depth. 3413
Comm. 7-29-36 Comp. 10-19-36
Shot or Treated. 2000 gal.
Contractor.
Issued. 11-14-36

CASING.

20" 57'
15 1/2" 531'
12 3/8" 1212'
10" 2462'
8 5/8" 2850'
7" 3307'

NOV 14 1936



Elevation.

Production. Pot. 219 B.
148 B. W.
after acid.

Figures Indicate Bottom of Formations.

clay	30	salt shells	1655	shale blue	2620
shale	40	salt	1815	lime	2635
sand HFW	62	shale	1825	shale blue	2645
shale	260	lime	1830	lime	2650
lime shells	265	shale	1840	shale blue	2690
slate	275	lime	1850	lime	2695
shale	360	shale	1860	shale blue cave	2725
sand water	375	lime shells	1880	lime	2730
shale	395	lime	1890	shale	2740
red rock	405	shale	1900	red rock	2750
shale	430	lime	1915	shale blue	2790
red rock wtr	445	shale	1920	shale blue HFW 2750	2800
sand	500	lime	1940	lime	2805
shale	531	shale	1945	shale dark	2850
lime	533	red rock	1975	lime	2860
sand wtr	555	lime	1995	shale	2865
sd shale	580	red rock	2025	lime	2870
shale	650	lime	2045	shale	2875
lime	660	shale	2065	lime	2888
shale	705	red rock	2128	shale lime shells	2905
shale blue mud	717	lime	2145	shale blue	2915
lime	720	shale	2150	lime broken	2925
sand water	747	lime	2160	shale	2975
shale	755	lime broken	2205	lime	2980
sand	775	red rock	2220	shale	2990
shale dark	785	lime	2225	lime	3035
sd shale	795	shale shells	2250	shale	3040
sand	825	lime shells	2260	lime	3062
shale blue	840	red rock	2265	lime	3225
lime	843	lime broken	2275	shale blue	3245
shale grey	848	lime shells	2285	lime	3265
red rock	865	lime	2300	red rock	3268
sand 6 BW	875	shale	2317	lime	3271
red rock	1100	lime	2330	small show oil 3268-71	
red rock	1195	red rock	2350	red rock	3275
anhydrite	1200	lime	2360	lime	3305
lime 10BW 990-1000	1237	red rock	2365	shale	3311
red rock	1310	lime	2370	lime	3346
HFW 1030-50		shale blue	2382	show oil 3311-17 equals 1/2	
shale	1335	lime	2388	Bbls oil per hr.	
red rock	1365	shale blue	2395	shale blue	3348
shale blue	1375	red rock	2435	2 BW 3317	
red rock	1390	lime	2452	Water 3325.	
lime	1393	shale	2458	3296 equals 3304 SLM.	
shale blue	1410	lime	2462	shale blue	3348
red rock	1440	lime	2470	lime	3404
shale	1450	shale	2475	3404 equals 3413 SLM.	
red rock	1475	lime	2495	Total D _o pth.	
lime	1483	shale	2500		
shale blue	1520	lime	2510	pay 3373-81 no inc. 3381-3413	
lime	1525	shale	2520	1000' oil 15 hrs.	
shale	1535	lime	2550		
lime	1570	shale	2560		
shale shells	1600	lime	2605		