

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - DARBY & BOTH ELL, INC.
Farm - Giebler "B" No. 1

SEC. 10 T. 13 R. 17W
NE NE SE

Total Depth. 3542'
Comm. 3-28-49 Comp. 4-25-49
Shot or Treated. Acidized
Contractor. Iron Drig. Co.
Issued. 5-21-49

County. Ellis

KANSAS



CASING:
8-5/8" 234' Cem. w/135 Sx.
5-1/2" 3516' Cem. w/100 Sx.

Elevation. 2010 feet

Production. 1301 bbls., Potential

Figures Indicate Bottom of Formations.

surface	234
shale	360
shale & shells	570
shale, sand & red rock	1185
anhydrite	1220
shale & shells	1510
lime & shale	2625
shale	2780
lime & shale	3018
lime	3047
lime & shale	3115
lime	3165
lime & shale	3375
lime	3516
dolomite	3520
Deepening Record:	
Arbuckle dolomite	3528
swab 2 BOPH, 3 hrs,	
500 acid, 850# to 600#	
Swab 2 1/2 BOPH, 3 hrs.	
Arbuckle dolomite	3542
swab 45 BO 5 hrs., 500	
acid 800# to 0#. Pot.	
1301 BO, no wtr	
Total Depth	3542'

Tops:	
Anhydrite	1185
Topeka	2972
Hoebner	3216
Lansing	3262
Arbuckle	3516

DST 3324-34, open 10 mins.
rec. 100' hvy oil cut mud
& good show gas, 950# BHP