

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - DARBY & BOWTHWELL
Farm - Giebler "B" No. 6

SEC. 10 T. 13 R. 17W
SW NE SE

Total Depth. 3531
Comm. 1-14-50 Comp. 2-3-50
Shot or Treated.
Contractor.
Issued. 4-8-50

County. Ellis
KANSAS



CASING: 8 5/8" 1172' cem w/500 sx.
5 1/2" 3507' cem w/100 sx.

Elevation. 1997(m)
1999 RB (ind)

Production Est. 50 Bbls.

	Figures Indicate Bottom of Formations.
Surface clay	40
Shale & shells	325
Sand	355
Shale & shells	630
Sand & shale	690
Sand	810
Shale & shells	1025
Red bed	1163
Anhydrite	1203
Shale & shells	1240
Red bed	1360
Shale & shells	1825
Shale & lime	2590
Shale & shells	2645
Shale & lime	2700
Shale	2795
Lime & shale	2960
Lime	3035
Lime & shale	3080
Lime	3110
Shale & lime	3230
Lime	3508
Lime	3531
Total Depth	

Tops:	
Anhydrite	1163
Topeka	2938
Heebner	3201
Dodge	3220
Lansing	3246
Arbuckle	3506

Rotary TD 35 08
Cable TD 3531
D.S.T. 3285-3320, open 30 min.
good blow, recover 105 ft. oil
& gas cut mud. 932# B.H.P.
D.S.T. 3320-3350, open 30 min.
good blow, recover 240 ft. oil
& gas cut mud B.H.P. 619#
1250 gals acid. Potential not
taken. Est. 50 bbl.