


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **CITIES SERVICE OIL CO.**
Farm- Dreiling No. 5

SEC. 22 T. 13 R. 17W
C N/2 N/2 NW
330' S & 1320' E of NW Corner

Total Depth. 3585'
Comm. 2-20-58 Comp. 4-9-58
Shot or Treated.
Contractor. Lohmann-Johnson Drlg.
Issued. 5-31-58

County Ellis
KANSAS



Elevation. 2006' Gr.

CASING:
8 5/8" 240' cem w/200 sx.
5 1/2" 3553' cem w/175 sx.
DV Tool 1276' w/325 sx cem & 175 cu. ft. Stratacrete.
Figures indicate Bottom of Formations.

Production. 94 Oil, no water,
24 hours.

sand & shale	100
shale & shells	240
shale & sand shells	1030
shale & sand	1240
anhydrite	1270
shale & shells	1890
shale & lime	2233
lime	3558
3558 Rotary TD = 3554 S.L.M.	
lime	3585
Total Depth	

TOPS: CORR.
Heebner 3261
Dodge 3281
Lansing 3308
Arbuckle 3551
Pen. 34'

Acid 1000 gals. 4-10-58