

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.  
Farm - L.J. Dreiling "D" No. 1

SEC. 22 T. 13 R. 17W  
NWc SW

Total Depth. 3682'

Comm. 5-1-47

Comp. 5-19-47


Shot or Treated.

Contractor. Kiowa Drlg. Co. Rotary 0-3683'

Issued. 6-7-47 Cable 3683-3682'

County. Ellis

KANSAS



Elevation. 1983 feet

CASING:

8 5/8" OD 1225' cem. w/550 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface, clay & sand	40
sand & clay	70
shale & shells	350
sand	375
shale & shells	670
sand	860
shale	880
shale & shells	1055
red bed	1085
shale & shells	1200
shale, shells & iron	1210
anhydrite	1255
shale	1325
shale & shells	1630
salt & shale	1750
shale & shells	1875
lime & shale	2070
lime	2290
shale	2305
lime brkn	2360
lime & shale	2570
shale & shells	2580
lime brkn	2635
lime & shale	2690
shale & shells	2820
lime & shale	2990
lime	3250
shale	3290
lime	3328
lime & shale	3348
lime	3385
lime & shale	3440
lime brkn	3480
lime	3554
lime, shale & chert	3569
cherty conglomerate	3623
lime	3650
lime & chert	3660
cherty lime	3682
Total Depth	

Tops:

Lansing	3319
Arbuckle	3622
Conglomerate	3566

Cored: 3348'-53', recovered 3' from  
3350'-51 1/2' porous lime w/spotted stain  
3351 1/2'-53' dense lime - Show oil 3638'-43'  
Ran DST, packer at 3625'50', 25' anchor,  
open 15 min., filled up 120' w/mud - Ran  
Schlumberger, no show. Plugged.  
(Complete Plugging 5-19-47)