


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Rome "B" No. 1
✓

SEC. 22 T. 13 R. 17 W
SW NW SW
990' S & 330' E of W/4 Cor.

Total Depth. 3536'
Comm. 4-2-47 Comp. 5-6-47
Shot or Treated. Acidized
Contractor. R. W. Rine Drilg. Co.
Issued. 7-26-47

County. Ellis
KANSAS



CASING:

8 5/8" 1215' Com. w/350 sx.
5 1/2" 3526' Com. w/75 sx.

Elevation. 1924' at top

Production. Phy. Pot. 451 BO, no
wtr., 24 hrs.

Figures Indicate Bottom of Formations.

clay & sand	0-50
shale & shells	450
lime	505
shale & shells	1209
anhydrite	1245
shale & shells	2170
lime & shale	2260
shale & shells	2470
shale & lime	2595
shale & shells	2925
shale	3034
shale & shells	3121
lime & shale	3412
lime	3537

3537 RTD=3527 SLM

lime 3536
Total Depth.

Tops:
Lansing 3299 Corr
Arbuckle 3526 Corr.
Penetration 10

Fillup:

650' oil in 1 1/4 hrs.
825' oil in 1 1/2 hrs.
1425' oil in 2 1/4 hrs.
1815' oil in 3 1/4 hrs.
200' oil in 4 1/4 hrs.
2350' oil in 5 1/4 hrs.
2610' oil in 7 hrs.

5-6-47 - Deepened 3531-36'.

500 gals. acid 4-26-47
1000 gals. acid 5-2-47
1000 gals. acid 5-8-47