

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 22 T. 13 R. 17W

LOC. NE SW SW

FARM Rome "B"

NO. 2

990' N & 990' E. of SWc

TOTAL DEPTH 3611

COMM. 4-14-51

COMP. 4-27-51


SHOT OR TREATED

CONTRACTOR

ISSUED 5-26-51

COUNTY Ellis

KANSAS



CASING

8 5/8" 1234' cem. w/550 sx

ELEVATION 1994

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

lime & shale	41
shale & shells	325
sand, shale & shells	570
shale & shells	690
sand	860
shale & shells	1020
red bed & shells	1220
anhydrite	1260
shale & shells	1640
salt, shale & shells	1795
shale & shells	1885
lime & shale	2215
shale & lime	2310
lime & shale	2480
shale & lime	2820
lime & shale	3065
lime	3560
cherty lime	3595
lime	3611
Total Depth	

Tops:	
Heebner	3258
Dodge	3294
Lansing	3319
Cherty Conglomerate	3561
Eros. Arbuckle	3575
Arbuckle	3581

Penetration 30'