

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. THE TEXAS COMPANY
Farm. L.J. Drilling "E" No. 1

SEC. 22
NW SW NW

T. 13

R. 17W

Total Depth. 3573'

Comm. 7-17-47

Comp. 8-11-47


Shot or Treated.

Contractor. Kiowa Drilg. Co.

Issued. 10-4-47

County. Ellis

KANSAS



2001nh

Elevation. 1997 ft

Production. 3230 Bbls oil

Figures Indicate Bottom of Formations.

surface clay, shale & sand	75
shale	370
sand	420
shale	480
sand, shale & shells	690
sand	860
shale & iron	975
red bed & iron	1230
anhydrite	1230
red bed	1450
shale	1650
salt	1775
shale & shells	1880
lime & shale	2090
lime	2110
shale & lime	2150
sandy lime	2195
lime	2330
lime & shale	2490
lime	2520
lime & shale	2540
lime	2665
lime & shale	2805
shale	2875
shale & lime	2980
lime	3314
lime & shale	3350
lime	3573
Total Depth.	

TOPS:

Anhydrite	1230
heebner	3252
Lansing	3295
Arbuckle	3542

REMARKS:

8-8-47 Acidized with 500 gallon
8-11-47 " " 1000 " 3550-3570,
3' blanket on bottom.