

KANSAS DRILLERS LOG

S. 31 T. 13 R. 17 ^K _W

API No. 15 — 051 — 21,247
County Number

Loc. SE NE NE

County Ellis

Operator
Raymond Oil Company, Inc.

Address
200 West Douglas, Suite 800 Wichita, Kansas 67202


Well No. #3 Lease Name Wiesner

Footage Location
990 feet from (N) line 330 feet from (E) line

Principal Contractor Geologist
Dreiling Oil, Inc. Chas. B. Spradlin

Spud Date Total Depth P.B.T.D.
11-17-76 RTD 3630 LTD 3628

Date Completed Oil Purchaser
11-24-76 Permian



Elev.: Gr. 2042

DF 2044 KB 2047

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9-5/8	8-5/8		202		150	
Production		5-1/2	14#	3628		200 200	60-40 Poz Hal Lite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DP jets	3378-82
			2	Ditto	3357-63

TUBING RECORD

Size	Setting depth	Packer set at
2"	3585	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 Gal.	3378-82
500 Gal.	3357-63

INITIAL PRODUCTION

Date of first production January, 1977	Producing method (flowing, pumping, gas lift, etc.) pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 50 bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) 3378-83 and 3428-30

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Raymond Oil Company, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

Well No. 3 Lease Name Wiesner

S 31 T13 R 17 E W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 30/45/45/60 Rec. 90' slightly OCM IFP 69-104 - ISIP 708 - FFP 115-115 - FSIP 708	3297	3365	<u>LOG TOPS</u> Anhy	1271
DST #2 30/45/45/60 Rec. 150' HOCM IFP 46-69 - ISIP 708 - FFP 81-104 - FSIP 708	3368	3385	B/Anhy Topeka Heebner	1310 3038 3288
DST #3 30/30/30/30 Rec. 65' slightly OCM IFP 46-58 - ISIP 242 - FFP 81-81 - FSIP 346	3391	3417	Toronto Lansing	3308 3331
DST #4 30/45/45/60 Rec. 130' slightly OCM IFP 46-81 - ISIP 242 - FFP 92-127 - FSIP 242	3420	3440	B/KC Congl.	3562 3583
DST #5 30/30/30/30 Rec. 30' mud - no sho IFP 92-92 - ISIP 369 - FFP 92-104 FSIP 288	3478	3560	Arb LTD	not penetrate 3628

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

RAYMOND OIL COMPANY, INC.
Wm M Raymond
 Wm. M. Raymond Signature
 President
 Title
 February 21, 1977
 Date