

32.13.17W


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DERBY OIL COMPANY
Farm - Lang No. 1

SEC. 32 T. 13 R. 17W
SW SW NE

Total Depth. 3698'
Comm. 1-31-48 Comp. 3-20-48
Shot or Treated. 500 acid
Contractor. G. W. Pool
Issued. 7-30-49

County. Ellis
KANSAS



CASING:

8 5/8" 1265' com. w/600 sx
5 1/2" 3584' com. w/100 sx

Elevation. 2045' Ind

Production. Dry

Figures Indicate Bottom of Formations.

All measurements taken from Kelly Bushing
which was above Bradon Head.

surface rock, clay	75	Small show oil. Acidized with
shale, shells	325	500 gallons. Swabbed trace
shale	350	oil and small amount water.
sand	415	Plugged and abandoned.
shale	460	
sand	498	
shale, sd strks	650	
pyrito, shale, sd strks	710	
sand	900	
shale, shells	940	
shale, shells, pyrito	1020	
shale, shells	1254	
anhydrite	1295	
shale, shells	1580	
shale, shale, strks	1890	
shale, limo	1945	
shale, strks limo	2105	
limo, brkn, shale	2163	
limo	2448	
shale, limo	2495	
shale, limo, strks	2645	
shale, limo	2730	
limo, shale	3025	
limo, shale, brkn	3076	
limo	3572	
conglomerate	3583	
arbucllo	3586	
limo	3588	
chert	3643	
limo	3698	
Total Depth		

TOPS:

Lansing	3373
arbucllo	3383

Show Oil	3323-3550
227' thick	3355-61 & 3020-25

Drill Stem Tests

Formation Tested	From	To	Results
Lansing	3418	3425	Rec. 30' oil cut mud

Completion Record

Drilled Cement and shoe to 3698'
Bailed 4 BW per hr.
Set Lane Wells Plug 3560.
Perf. 32 shots 3533-36 and 3418 -26