

32. 13. 17W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - BEN F. BRACK OIL CO., INC.
Farm - Lang No. 1

SEC. 32 T. 13 R. 17W
NW NW NW

Total Depth. 3660
Comm. 6-15-51 Comp. 6-29-51
Shot or Treated.
Contractor.
Issued. 7-28-51

County. Ellis



CASING:
8 5/8" 314'

Elevation. 2047 DF
2049 RB (rod)
Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	250
shale, shells	314
shale & sand	740
sand	925
red bed & shale	1070
sand, shale & red bed	1305
shale, shells & red bed	1650
salt	1740
salt, shale & shells	2020
lime & shale	2100
broken lime	2250
lime & shale	2420
broken lime & shale	2515
lime & shale	2825
shell & shells	2955
lime & shale	3280
lime	3505
lime & shale	3565
lime	3660
Total Depth	
Tops:	
Lansing	3323
Conglomerate	3587

No Arbuckle was encountered
to depth of 3660'