

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


34.13.11W

Company- EL DORADO REFINING CO.
Farm- Braun No. 2

SEC. 34 T. 13 R. 17W
NW SE NE

Total Depth. 3515
Comm. 10-12-51 Comp. 11-12-51
Shot or Treated.
Contractor. Pickrell Drlg. Co.
Issued. 1-5-52

County Ellis
KANSAS



CASING:

8 5/8" 348' cem w/175 sxs.
5 1/2" 3370' cem w/110 sxs.

Elevation. 1968 DE

Production. 75 BOPD

Figures indicate Bottom of Formations.

cellar	5
rock, clay, shale	105
shale, shells	348
sand, shale, sandy	
shale	575
iron, shale	615
sand, shale	855
sandy shale, sand	1095
anhydrite	1140
shale, sand	1155
shale, shells	1615
lime, shale	2180
lime	2290
lime, shale	2485
shale, shells	2600
shale, shells, lime	2735
shale, lime	3126
lime	3515 RTD
Total depth	

Tops:

Hoebner	3191
Toronto	3209
Lansing	3240
Conglomerate	3481

DST 3247-71, open 20 min.
rec. 100' hvy. O & GCM
600' oil, 80' wtr. &
2300' gas BHP 865#

DST 3305-18, op. 30 min.
rec. 120' hvy. OCM & 360'
gas BHP 830#

DST 3328-36, op. 1 hr. rec.
90' muddy wtr. BHP 1030#

DST 3365-77 op. 45 min.
rec. 50' mud, BHP #0

Cleaned out & perf. (8)
3308-10 (16) 3312-16

1000 gals. acid ϕ 3 1/2 BOPH;
4000 gals. acid, ϕ 6 1/2 BFP
1/2 hr./ 6 hrs.

DM@ 3280, squeeze; set plug & perf.
(16) 3262-66 ϕ 5 BFP/2 hrs.