

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- EL DORADO REFG. CO.
Farm- Braun No. 3

SEC. 34 T. 13 R. 17W
NE NE NE

Total Depth. 3785'

Comm. 10-23-51

Shot or Treated.


Contractor. Pickrell Drlg. Co.

Issued. 6-7-58

DEEPENING RECORD:

Comp. 11-26-51

County Ellis
KANSAS



Elevation. 1978 DF

Production. 50 BOPD

CASING:

8 5/8" 352' cem w/180 sx
5 1/2" 3510' cem w/100 sx

Figures indicate Bottom of Formations.

sand, shale, shells	175
shale, shells	600
iron	650
sand	805
red rock, shale	885
shale, shells	1028
anhydrite	1050
shale, shells	1820
lime	1955
limc, shale	2135
lime	2450
lime, shale	2760
lime	3510 RTD
lime	3533
Total Depth	

TOPS: DF

Heebner	3212
Toronto	3228
Lansing	3260
Arbuckle	3502
No. Cg.	

DST 3270-90, op. 1 hr. rec.
58' muddy salt wtr. slight
blow/1 hr. BHP 928#

DST 3318-40, op. 1 hr. rec.
8' mud, 4' FO light blow BHP
50# 15 min. & building up.

DST 3388-3400, op. 1 hr. rec.
45' sli. OCM, BHP 80#/15 min.
C.O. to RTD odor no show;
DD 3525; SO 3522-25 1 blr. PH.
DD 3528, 1/2 - 2/3 BOPH; DD 3533,
increase in oil 3529 1/2-33; 1 1/2
NOPH/2 hrs. 500 acid 2 1/2 BOPH/5
hrs.

DEEPENING RECORD:

Comm-11-8-54
Comp-12-20-54
Prod- SWIW
T.D.-3785'
Clean-out to 3533 & acid-frac
w/3000 gals.-Tested 5.35 EW & 1/2 BOPH
10 hrs.

Old T.D.	3533
cherty dolomite w/Tr	
sand	3545
red shaly dolomite	3636
dolomite	3766
shaly dolomite	3785
Total Depth	