


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. THE EL DORADO REINING CO.
Farm. Braun "A" No. 5

SEC. 34 T. 13 R.17W
SE NW NE

Total Depth. 3496
Comm. 5-6-53 Comp. 5-18-53
Shot or Treated.
Contractor. Anschutz Drilling Co.
Issued. 7-4-53

County Ellis
KANSAS



CASING:

8 5/8 set at 320' w/ 200 sx cement
5 1/2 set at 3471' w/ 100 sx cement

Elevation. 1968 DF

Production. 100 bbls. / 8 hrs.

Figures indicate Bottom of Formations.

surface clay	40
shale	460
sand & shale	675
sand	793
shale	920
shale, shells & red bed	1130
shale & red bed	1155
anhydrite	1195
shale & shells	1405
shale	1720
shale & shells	1915
lime	2035
shale & lime	2110
lime	2355
lime & shale	2563
broken lime	2655
shale & lime	2740
shale	2940
lime	3473 DF. RTD
Arbuckle	3496
Total Depth	

TOPS:

Anhydrite	1155
Arbuckle	3179
Arbuckle	3199
Arbuckle	3226
Arbuckle	3470

DST #1: 3318-27, open 1 hr. rec.
30' lightly O&GCM, BHP 240#

DST #2: 3354-78, open 1 hr. rec.
65' BHO&GCM, BHP 975#

DST #3: 3400-32, open 1 hr. rec.
90' VHO&GCM, BHP 975#

GO to btm. NSDD 3476, rbo SO; DD 3379,
goo rbo SO; DD 3481, VSSO, DD 3383
VSSO, tst 1 1/2 GOPH/2hrs. DD 3486, 2 1/2
GOPH/5hrs. 500 acid, no inc. DD 3496, TD
incr. oil 3489-93, 1000 acid; 13.36
BO/8 hrs. Oil & sandfracked, 3.75
BOPH/ 5hrs. P. B. 3445, perf. (18)
3400-13, (27) 3406-10, 1000 acid.
Avgd. 15.86 BOPH/ 8hrs.