

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- BIRMINGHAM-BARTLETT DRG. CO.  
Farm- Sanders No. 5

SEC. 35 T. 13 R. 17W  
SE SE NW

Total Depth. 3515'  
Comm. 5-17-56 Comp. 5-26-56  
Shot or Treated.  
Contractor. Birmingham-Bartlett Drlg.  
Issued. 6-30-56

County Ellis

KANSAS



Elevation. 3515' RB

CASING:

8 5/8" 175' cem w/175 sx

Production. Dry

Figures indicate Bottom of Formations.

clay and sand	140
shale & shells	175
shale, shells & sand	800
anhydrite	1185
shale and shells	1750
broken lime	1880
lime and shale	3045
lime	3499
Conglomerate	3515
Total Depth	

Tops:

Anhydrite	1150
Heebner	3198
Toronto	3219
Lansing	3245
Conglomerate	3494

DST #1 3247-79', open 1 hr., weak steady  
blow throughout. Rec. 180' gas & 100'  
muddy water BHP 770

DST #2 3278-98', open 30 mins. weak blow  
for 4 min. Rec. 15' mud. BHP 910#.

DST #3 3311-22', open 1 hr. weak steady  
blow throughout. Rec. 30' mud with specks  
oil. BHP 0#.