


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION CO.
Farm- Kuhn No. 1

SEC. 36 T. 13 R. 17W
NW NW SW

Total Depth 3595'
Comm. 9-3-57 Comp. 9-14-57
Shot or Treated.
Contractor. Strata Drlg.
Issued. 11-23-57

County Ellis
KANSAS



CASING:
8 5/8" 212' cem w/100 sx.

Elevation. 1953' RB

Production. Dry

Figures indicate Bottom of Formations.

surface soil & sand	60
shale & shell	209
shale & sand	850
red bed	1025
red bed	1135
shale & shell	1800
lime & shale	3065
lime	3546
lime & shale	3550
chert & shale	3595
Total Depth	

TOPS:
Topeka 2937
Heebner 3192
Toronto 3212
Lansing 3240
Base Kansas City 3468
Conglomerate 3490

Ran Electric Log.

DRILL STEM TESTS:

- #1 3242-80', shut in 20 min., rec. 15'
rtry mud. FP 0, BHP 400#.
- #2 3294-3310', open 1 hr., shut in 20 min.
rec. 6' mud. FP 24#, BHP 393#.
- #3 3317-35', open 1 hr. shut in 20 min.
rec. 9' mud. FP 30#, IBHP 988#,
FBHP 91#.
- #4 3380-3424', open 1 hr., rec. 8' mud.
FP 40#, BHP 42#.