

WICHITA BRANCH

OPERATOR: TGT Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Wiesner "A" #1
 LOCATION: 330' S of C SE Section 31-13S-17W
 Ellis County, Kansas
 SPUD DATE: June 29, 1978
 COMPLETION DATE: July 6, 1978

0	990	Shale & sand
990	1252	Shale
1252	1287	Anhydrite
1287	2015	Shale
2015	2199	Shale & lime
2199	3610	Lime
	3610	Rotary Total Depth

Spud hole at 4:00 p.m., June 29, 1978. Drilled 214' of 12¼" hole. Ran 5 joints of 8-5/8" surface casing. Set at 213' K.B. with 150 sacks common cement, 3% CaCl, 2% gel. Job complete at 10:30 p.m., June 29, 1978.

T.D. 3610'. Set first plug at 500' with 50 sacks, second plug at 185' with 25 sacks, 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 2% gel. Plug was down at 10:00 a.m., July 6, 1978.

SAMPLE TOPS:

Anhydrite 1252'
 B/Anhydrite 1289'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Wiesner "A" #1, 330' S of C SE Section 31-13S-17W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge, Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state