

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TRANSIT CORPORATION ET AL
Farm- Albert Weber No. 1

SEC. 33 T. 13 R. 17W
SE NW NW

Total Depth. 3568'

Comm. 12-18-55

Comp. 12-29-55


Shot or Treated.

Contractor. Transit Corp.

Issued. 5-10-58

County Ellis

KANSAS



Elevation. 2031' KB

Production. 36 BOPD

CASING:

8 5/8" 146' cem w/75 sx.
5 1/2" 3558' cem w/110 sx.

Figures Indicate Bottom of Formations.

surface	10
lime	40
shale	420
sand & shale	770
sand	890
red shale	1140
shale & red bed	1230
Anhydrite	1270
shale & red bed	1415
shale & lime	1660
shale & salt	1780
shale & salt	1865
shale & lime	2150
lime & shale	2460
shale & lime	2700
shale & lime	3150
lime	3272
soft shale	3276
shale	3294
lime	3310
lime & shale strks	3400
lime & shale	3550
red shale	3556
lime	3562 RTD
lime	3568
Total Depth	

TOPS:

Anhydrite (scout)	1230
Base Anhydrite (scout)	1270
Topeka Lime	3023
Heebner Shale	3272
Toronto Lime	3294
Lansing Lime	3316
Base Kansas City Lime	3502
Conglomerate	3550
Arbuckle Dolomite	3556