


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company CITIES SERVICE OIL CO.
Farm - Anderson "C" No. 2

SEC. 11 T. 13 R. 17W
NW SW NW
990' N. & 330' E of W/4 cor.

County. Ellis

KANSAS



Total Depth. 3630 P.B. 3485½'
Comm. 11-19-49 Comp. 12-2-49
Shot or Treated. 2500 gals. acid
Contractor. Holm Drlg.
Issued. 2-25-50

CASING:

8 5/8" 1190' cem. w/500 sx.
5 1/2" 3620' cem. w/200 sx.

Elevation. 2014 feet.

Phys. pot.

Production. 37 oil, 10 wtr. 2½ hrs.

Figures Indicate Bottom of Formations.

sand & shale	75
shale & shells	325
shale, shells & sand	550
shale & shells	720
sand	830
shale	895
red bed & shells	1180
anhyd.	1220
shale & shells	1580
salt, shale & shells	1735
shale & shells	1865
shale & l me	1955
lime & shale	2315
lime	2390
shale & lime	2550
shale	2650
shale & shells	2935
lime	3571
congl.	3584
lime	3630
Total Depth SLM Pl. B.	3485½'

Tops:

Lansing	3278
sandy congl.	3539
cherty congl	3556
Arbuckle	3615

Pen. 15'

Drilled cem. to 3590 SLM

Perf. 8 shots 3489-96, show wtr.
15 " 3477-82, show oil.
34 " 3465-74, " "
39 " 3446-58, " "

Plugged back with sand & cement to 3485½ SLM

12-21-49 Acidized 1000 gals. 3465-82.
12-28-49 " 1500 " 3446-58.
12-30-49 Pumped 28 oil. 3 wtr. 7 hrs.