

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock, Wichita, Kansas


Company: CITIES SERVICE OIL CO.  
Farm: Anderson "C" No. 1

SEC. 11 T. 13 R. 17W  
SW SW NW  
330' N & 330' E of W/4 cor

Total Depth. 3544  
Comm. 8-19-49 500 gals. ~~9-10-49~~ <sup>9-13-49</sup> at 3538  
Shot or Treated. Acid 1000 gals 9-14-49 at 3544  
Contractor. Holm Drlg.  
Issued. 1-28-50

County. Ellis

KANSAS



Elevation. 2016 *Ind.*

Production. Phys. Pot. 367 oil  
no wtr. 24 hrs.

CASING:

8 5/8" 1210 cem. w/450 sx.  
5 1/2" 3532 cem. w/150 sx.

Figures indicate Bottom of Formations.

lime	45
shale & shells	315
shale, shells, & sand	725
sand	840
sand & shale	890
red bed & shells	1185
anhyd.	1220
shale & shells	1590
salt, shale & shells	1725
shale & shells	1870
shale & lime	2220
lime	2395
lime & shale	2855
lime	3355
cherty lime	3410
lime	3528
3528 RTD = 3532 SLM	
lime	3544
Total Depth	

Tops:

Corr. Lansing 3273  
" Arbuckle 3530

Penetration 14'

Fillup:

140' oil in 30 mins. at 3538  
225' oil in 1 hr. 5 mins. at 3538  
400' oil in 1 hr. 40 mins. at 3535  
540' oil in 2 hrs. 5 mins. at 3538

9-9-49 Pumped 68 oil, no wtr, 9 hrs.  
9-10-49 Acidized 500 gals.  
9-11-49 Pumped 150 oil, 12 acid wtr. 10 hrs.  
9-13-49 Deepened 3538-3544.  
9-14-49 Acidized 1000 gals.