


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **WILKINSON DRILLING**
 Farm- **Dreiling** No. **2**

SEC. **11** **T.** **13** **R.** **17W**
 NW **SW** **SW**

Total Depth. **3615'**
 Comm. **8-17-57** Comp. **8-27-57**
 Shot or Treated.
 Contractor. **Wilkinson Drlg.**
 Issued. **5-16-59**

County **Ellis**
 KANSAS



CASING:
 8" **207'**
 5" **3602'**

Elevation. **2017' DF**

Production. **25 BOPD**

Figures Indicate Bottom of Formations.

DRILLERS LOG NOT AVAILABLE:

3279-3286' cream-gray-finely crystalline to dense limestone 3306-3311' gray sub-oolitic & sub-oolicastic limestone - lgt stain - slight odor 3350-3356' limestone as above 3359-3364' limestone as above 3370-3376' white to gray oolitic & oolicastic limestone - dk stain-good odor 3410-3415 gray-buff oolitic & oolicastic limestone-lgt, spotty stain no odor 3532-3536' gray-buff - finely crystalline dolomite - lgt stain-slight odor 3536-3540' dolomite as above- increase in staining 3540-3545' buff-finely crystalline dolomite good stain-odor 3549-3552' buff-fine to medium crystalline dolomite-good show free oil -- strong odor 3552-3557' dolomite as above-traces green- gray shale 3572-3590' buff-fine, coarse crystalline dolomite-lgt stain-weak odor TOTAL DEPTH 3615'	DST #7 3545-3557', op 30 mins., shut in 15 mins, weak blow 17 mins., rec. 25' of mud w/show of oil. DST #8 3570-3590', op 90 mins, shut in 30 mins, strong blow through test - rec. 1069' of water, FP 48-498# BHP 704#.
--	--

TOPS:	SAMPLE	ELECTRIC
Anhydrite (scout) 1135		
Heebner	3231	3233
Toronto	3252	3254
Lansing	3277	3279
Conglomerate	3524	3526
Arbuckle	3530	3532

DST #1 3254-3264', op 1 hr, shut in 20 mins
 good blow immediately-rec. 50' water w/a few
 specks live oil - all pressures - zero

DST #2 3388-3415' op 30 mins., shut in
 15 mins, rec. 25' of mud - flow pressure
 0-25# - bottom hole pressure 55#.

DST #3 3522-3536', op 30 mins., weak blow
 1 min, rec 5' mud - all pressures - zero

DST #4 3523-3540', op 30 mins, shut in
 15 mins, rec. 15' mud - all pressures -
 zero.

DST #5 3534-3545', op 30 mins., shut in
 15 mins, rec. 6' mud, all pressures - zero

DST #6 3535-3552', op 30 mins, shut in
 15 mins, weak blow 12 mins, rec. 2' very
 heavy oil cut mud - 20' mud. FP 18-18#
 BHP 120#.